Proposed Subdivision Brush Creek Estate - Precinct 2, Stage 5 Site Classification

Transfield Avenue, Edgeworth

NEW18P-0170B-AC
19 January 2021

Qualtest
LABORATORY (NSW) PTY LTD

GEOTECHNICAL I LABORATORY I EARTHWORKS I QUARRY I CONSTRUCTION MATERIAL TESTING

19 January 2021

McCloy Edgeworth Pty Ltd
Suite 2, Ground Floor, 317 Hunter Street
NEWCASTLE NSW 2300

Attention: Mr Jon Hines

Dear Sir

RE: PROPOSED SUBDIVISION - BRUSH CREEK ESTATE – PRECINCT 2, STAGE 5 TRANSFIELD AVENUE, EDGEWORTH GEOTECHNICAL ASSESSMENT

Please find enclosed our Geotechnical Assessment report for Lots 501 to 524 within Precinct 2, Stage 5 of the Brush Creek Estate, located off Transfield Avenue, Edgeworth.

The report includes recommendations on site classification in accordance with AS2870-2011, '*Residential Slabs and Footings'* for Stage 5 (lots 501 to 524).

If you have any questions regarding this report, please do not hesitate to contact Ben Edwards, Shannon Kelly or the undersigned.

For and on behalf of Qualtest Laboratory (NSW) Pty Ltd

Jason Lee
Principal Geotechnical Engineer

Table of Contents:

Attachments:

1.0 Introduction

Qualtest Laboratory NSW Pty Ltd (Qualtest) is pleased to present this geotechnical report on behalf of McCloy Edgeworth Pty Ltd (McCloy), for Precinct 2, Stage 5, of the Brush Creek Estate, located off Transfield Avenue, Edgeworth.

Based on the brief and drawings provided by the client, Stage 5 is understood to comprise of twenty-four residential allotments (Lots 501 to 524), as shown on the attached Figure AC1.

The scope of work for the geotechnical investigation included providing site classification with respect to reactive soils, in accordance with the requirements of AS2870-2011 '*Residential Slabs and Footings*', following completion of site regrade works.

This report presents the results of the field work investigations and laboratory testing, and provides recommendations for the scope outlined above.

2.0 Desktop Study

The scope of work has included a review of the following reports completed by Qualtest:

- Geotechnical Assessment, 'Proposed Subdivision, Brush Creek Estate – Precinct 2, Transfield Avenue, Edgeworth, (Report Reference: NEW18P-0170A-AA.Rev1, dated 4 March 2020);
- Geotechnical Investigation, 'Proposed Edgeworth Gravity Sewer Main' – Patterson Street to Minmi Road, Edgeworth, (Report Reference: NEW18P-0076-AB, dated 19 June 2018).
- Level 1 Site Regrade Assessment Report, 'Proposed Subdivision of Brush Creek Estate – Stage 5, Edgeworth, (Report Reference: NEW20P-0093-AA, dated 4 December 2020).

This report includes a summary of selected results from the previous reports. Reference should be made to the reports outlined above for further details of site description, subsurface conditions, field work conducted, engineering logs of test pits / boreholes, laboratory testing results, site supervision and density testing carried out.

3.0 Field Work

Field work investigations was carried out on 5 January 2021 and comprised of:

- DBYD search, review of plans, and visual check of proposed test locations for the presence of underground services;
- Site walkover to make observations of surface features at the property and in the immediate surrounding area;
- Excavation of 23 boreholes (BH501 to 513 and 515 to 524) using a 2.7 tonne excavator equipped with a 300mm diameter auger attachment. Boreholes were terminated at depths of between 0.42m and 2.00m;
- Undisturbed samples (U50 tubes) and small bag samples were taken for subsequent laboratory testing; and,
- Boreholes were backfilled with the excavation spoil and compacted using the excavator auger and tracks.

Investigations were carried out by an experienced Geotechnical Engineer from Qualtest who located the boreholes, carried out the sampling and testing, produced field logs of the boreholes, and made observations of the site surface conditions.

Engineering logs of the boreholes are presented in Appendix A.

Approximate borehole locations are shown on the attached Figure AC1. Boreholes were located in the field by handheld GPS and relative to existing site features including topographic features, lot boundaries, existing developments and trees.

4.0 Site Description

4.1 Site Regrade Works

Site re-grading for Stage 5 bulk earthworks was conducted between 27 August 2020 and 23 October 2020.

Re-grading works consisted of the removal of unsuitable materials, blending colluvium materials with site won Residual and stockpiled materials, along with cutting and filling activities to bring proposed residential lots within Stage 5 to design finish levels.

Re-grade works performed during the current Stage 5 bulk earthworks included filling within all or portions of Lots 501 to 505, 510 to 514 and 521 to 522. Refer to attached Figure AC1 for the approximate extent of lot filling works for this stage of the development.

Prior to filling, re-grade areas were stripped of all topsoil and unsuitable material to expose the suitable natural foundation profile, re-grade works then consisted of filling with approved site fill to design finish levels.

Filling was performed using site stockpiled material won from excavations cut and blended from around the site. The fill material could generally be described as mixtures of Residual (CI-CH) Gravelly Sandy CLAY and Extremely Weathered (EW) Siltstone / Sandstone, medium to high plasticity, brown / yellow / orange in colour, with fine to coarse grained sand and gravel, which was blended with a pale to dark brown Silty SAND (Colluvium).

The depth of fill placed ranged in the order of 0.1m to about 1.5m, with the following approximate maximum depths within each lot area outlined below:

- Lot 501 to Lot 503 - 1.5m;
- Lot 504 - 1.2m;
- Lot 505 - 1.5m;
- Lot 510 - 0.3m;
- Lot 511 to Lot 512 - 1.2m;
- Lot 513 to Lot 514 - 0.3m;
- Lot 521 - 0.9m; and
- Lot 522 - 0.3m.

The fill was compacted in maximum lifts of 0.3m thickness. Any unsuitable or deleterious material within the fill was removed by hand or mechanical means prior to final compaction of the material.

Refer to site regrade letter (Qualtest Report Reference: NEW19P-0093-AA, dated 4 December 2020) for full details including the approximate limit of filling works for this stage of the project.

As the geotechnical testing authority engaged for the project, we state that the re-grading works performed within Stage 5 (as shown on attached Figure AC1), was carried out to Level 1 criteria as defined in Clause 8.2 – Section 8, of AS3798-2007, "Guidelines on Earthworks for Commercial and Residential Developments".

The recommendations of this report are based on the understanding that any existing lot re-grade works are limited to the controlled earthworks supervised by Qualtest, and placement of low reactivity topsoil material such that total depth of topsoil and uncontrolled fill does not exceed 0.4m. Qualtest should be informed without delay if additional earthworks are known to have been carried out.

4.2 Surface Conditions

The site comprises Precinct 2, Stage 5 of the proposed residential subdivision known as Brush Creek Estate – located off Transfield Avenue, Edgeworth, as shown on Figure AC1 attached.

The site is bounded to the east by dense bushland, to the north and west by Future Stage 6 (under construction), and to the South by recently constructed sediment basin, an existing creek (Brush Creek) and Watalong Way.

Trafficability was judged to be good by way of 4WD vehicle along the existing sealed roads.

Photographs of the site taken on the day of the site investigations are shown below.

Photograph 1: From near BH505, facing southwest.

Photograph 2: From near BH505, facing west.

Photograph 3: From near BH501, facing northwest.

Photograph 4: From near BH501, facing north.

Photograph 5: From near BH523, facing northeast.

Photograph 6: From near BH523, facing east.

Photograph 7: From near northern boundary of Lot 521, facing southeast.

Photograph 8: From near northern boundary of Lot 521, facing southwest.

4.3 Subsurface Conditions

Reference to the 1:100,000 Newcastle Coalfield Regional Geology Series Sheet 9231 indicates the site to be underlain by the Adamstown Subgroup (majority of site) of the Newcastle Coal Measures, which are characterised by Conglomerate, Sandstone, Siltstone, Coal and Tuff rock types. The southern portion of Stage 5 associated with Brush Creek is indicated to be underlain by Quaternary aged Alluvial soils comprising mixtures of Gravel, Sand, Silt and Clay.

Table 1 presents a summary of the typical soil and rock types encountered at borehole locations during the field investigation, divided into representative geotechnical units.

Table 2 contains a summary of the distribution of the geotechnical units at the borehole locations.

TABLE 1 – SUMMARY OF GEOTECHNICAL UNITS AND SOIL / ROCK TYPES

Unit	Soil Type	Description
1A	FILL – TOPSOIL, MULCH	Gravelly Sandy CLAY – low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel. Tree mulch overlying Fill-Topsoil in places.
1B	FILL - UNCONTROLLED	SAND – fine to coarse grained, pale grey. Sandy CLAY – medium to high plasticity, grey to brown and orange, fine to coarse grained sand.
1C	FILL - CONTROLLED	Gravelly Sandy CLAY / Clayey SAND – low to medium plasticity, pale brown to brown, trace grey to pale grey and orange, fine to coarse grained sand, fine to coarse grained (mostly fine to medium grained) angular to sub-angular gravel. Sandy CLAY / Gravelly CLAY / CLAY – medium to high plasticity, pale grey and pale orange-brown to orange and red-brown, grey-brown, fine to coarse grained sand (mostly fine grained), with fine to coarse grained gravel in places. Sandy GRAVEL – fine to coarse grained angular to sub-angular, brown to pale brown, fine to coarse grained sand, with some fines of low to medium plasticity.
2	COLLUVIUM	Gravelly SAND – fine to coarse grained, grey, fine to medium grained rounded to sub-rounded and sub-angular gravel.
3	RESIDUAL SOIL	Sandy CLAY / CLAY – medium to high plasticity, pale grey with pale orange to orange, fine to coarse grained sand, trace fine to medium grained angular gravel. Gravelly Clayey SAND – fine to coarse grained, pale grey and orange, fines of low plasticity, fine to coarse grained angular to sub-angular gravel. Silty CLAY / Sandy CLAY / Clayey SAND – low to medium plasticity, pale grey and pale orange to orange, fine to coarse grained sand, trace fine to medium angular to sub-rounded gravel.
4	EXTREMELY WEATHERED (XW) ROCK with soil properties	Siltstone; breaks down into Gravelly Sandy CLAY – low to medium plasticity, pale grey and pale orange, fine to coarse grained sand, fine to medium grained angular to sub-rounded gravel.
5	HIGHLY WEATHERED (HW) ROCK	Sandy SILTSTONE – pale grey and pale orange to orange, estimated very low to medium strength (mostly low to medium strength). Extremely weathered pockets in places.

TABLE 2 – SUMMARY OF GEOTECHNICAL UNITS ENCOUNTERED AT BOREHOLE LOCATIONS

Location	Unit 1A FILL: TOPSOIL, MULCH	UNIT 1B FILL - CONTROLLED	UNIT 1C FILL - UNCONTROLLED	UNIT 2 COLLUVIUM	Unit 4 RESIDIAL SOIL	Unit 5 XW ROCK	Unit 6 HW ROCK
	Depth in metres (m)						
Current Investigation (January 2021)							
BH501	0.00 – 0.10	0.10 – 1.80	-	1.80 – 2.00	-	-	-
BH502	0.00 – 0.30	0.30 – 1.60	-	-	1.60 – 2.00	-	-
BH503	0.00 – 0.30	0.30 – 1.40	-	-	1.40 – 1.80*	-	-
BH504	0.00 – 0.30	0.30 – 1.30	-	-	1.30 – 2.00*	-	-
BH505	0.00 – 0.30	0.30 – 1.80	-	-	1.80 – 2.00	-	-
BH506	0.00 – 0.40	-	-	-	0.40 – 0.60	-	0.60 – 0.65*
BH507	0.00 – 0.20	-	-	-	0.20 – 1.10	-	1.10 – 1.15*
BH508	0.00 – 0.30	-	-	-	0.30 – 1.10	1.10 – 1.40	1.40 – 1.42*
BH509	0.00 – 0.30	-	-	-	0.30 – 0.80	-	0.80 – 0.82*
BH510	0.00 – 0.30	0.30 – 0.90	-	-	0.90 – 2.00	-	-
BH511	0.00 – 0.20	0.20 – 1.00	-	-	1.00 – 2.00	-	-
BH512	0.00 – 0.30	-	-	-	0.30 – 1.00	-	-
BH513	0.00 – 0.30	-	0.30 – 0.40	-	0.40 – 1.10*	-	-
BH515	0.00 – 0.30	-	-	-	0.30 – 0.90	-	0.90 – 0.92*
BH516	0.00 – 0.20	-	-	-	0.20 – 0.60	-	0.60 – 0.62*
BH517	0.00 – 0.25	-	-	-	0.25 – 0.50	-	0.50 – 0.52*
BH518	0.00 – 0.40	-	-	-	-	-	0.40 – 0.45*
BH519	0.00 – 0.30	-	-	-	-	0.30 – 0.40	0.40 – 0.45*
BH520	0.00 – 0.20	-	0.20 – 0.30	-	0.30 – 0.40	-	0.40 – 0.42*
BH521	0.00 – 0.20	0.20 – 0.80	-	-	0.80 – 1.80*	-	-

Location	Unit 1A FILL: TOPSOIL, MULCH	UNIT 1B FILL - CONTROLLED	UNIT 1C FILL - UNCONTROLLED	UNIT 2 COLLUVIUM	Unit 4 RESIDIAL SOIL	Unit 5 XW ROCK	Unit 6 HW ROCK
	Depth in metres (m)						
BH522	0.00 – 0.20	0.20 – 0.40	-	-	0.40 – 1.30	-	1.30 – 1.35*
BH523	0.00 – 0.20	0.20 – 0.60	-	-	0.60 – 1.90	-	1.90 – 2.00*
BH524	0.00 – 0.30	-	-	-	0.30 – 1.50*	-	-
Previous Investigation (Ref: NEW18P-0170B-AC, 4 March 2020) – Prior to site regrade works							
TTP20	0.00 - 0.30	-	-	0.30 - 0.60	0.60 - 2.15	2.15 - 2.30	-
TTP21	0.00 - 0.10	-	-	0.10 - 0.60	0.60 - 2.40	-	-
TTP22	0.00 - 0.30	-	-	0.30 - 0.70	0.70 - 2.50	-	-
TTP23	0.00 - 0.10	-	-	0.10 - 0.40	0.40 - 2.50	-	-
TTP24	0.00 - 0.25	-	-	-	0.25 - 0.70	0.70 - 0.95	0.95 - 1.05#
TTP26	0.00 - 0.20	-	-	0.20 - 0.40	0.40 - 0.65	-	0.65 - 1.00#
TTP27	0.00 - 0.30	-	-	-	0.30 - 0.60	-	0.60 - 0.85#
TTP28	0.00 - 0.20	-	-	0.20 - 0.40	-	0.40 - 1.00	1.00 - 1.30#
TTP29	0.00 - 0.15	-	-	0.15 - 0.50	0.50 – 0.95	-	0.95 - 1.00#
Previous Investigation (Ref: NEW18P-0076, 5 June 2018) – Prior to site regrade works							
BH20	0.00 - 0.30	-	-	0.30 - 0.60	0.60 - 2.15	2.15 - 2.30	-
BH21	0.00 - 0.10	-	-	0.10 - 0.60	0.60 - 2.40	-	-
Notes:	* = Practical refusal to Refusal of V-bit auger drill met on Highly Weathered Rock. # = Practical refusal or refusal of 20 tonne excavator met on Highly Weathered Rock.						

Groundwater levels or inflows were not encountered in boreholes during the limited time that they remained open on the day of the field investigations.

It should be noted that groundwater conditions can vary due to rainfall and other influences including regional groundwater flow, temperature, permeability, recharge areas, surface condition, and subsoil drainage.

5.0 Laboratory Testing

Samples collected during the field investigations were returned to our NATA accredited Warabrook Laboratory for testing which comprised of:

- (13 no.) Shrink / Swell tests; and
- (4 no.) Atterberg Limits tests;

Proposed shrink/swell testing for a number of samples were replaced by Atterberg Limits classification tests due to the friable nature of the site soils.

Results of the laboratory testing are presented in Appendix B, with a summary of the Shrink/Swell and Atterberg Limits test results presented in Table 3 and Table 4, respectively.

TABLE 3 – SUMMARY OF SHRINK/SWELL TESTING RESULTS

Location	Depth (m)	Material Description	I_{ss} (%)
Current Investigation			
BH502	0.50 – 0.70	FILL: (CL) Gravelly Sandy CLAY	0.7
BH503	1.20 – 1.37	FILL: (CL) Gravelly Sandy CLAY	0.8
BH504	1.50 – 1.60	(CH) CLAY	2.3
BH507	0.40 – 0.55	(CH) CLAY	3.0
BH508	0.50 – 0.75	(CH) CLAY	1.8
BH509	0.30 – 0.50	(CH) CLAY	2.2
BH510	0.70 – 0.90	FILL: (CH) CLAY	2.7
BH513	0.50 – 0.70	(CH) CLAY	1.5
BH515	0.40 – 0.55	(CH) CLAY	2.7
BH521	0.50 – 0.65	FILL: (CL) Gravelly Sandy CLAY	0.7
BH522	0.80 – 1.00	(CH) CLAY	1.4
BH523	1.00 – 1.15	(CH) CLAY	1.8
BH524	0.50 – 0.65	(CH) CLAY	1.8
Previous Investigation (Ref: NEW18P-0170B-AC, 4 March 2020)			
TPP20	0.80 - 0.90	(CH) Sandy CLAY	1.2
TPP21	0.60 - 0.95	(CH) Sandy CLAY	0.1
TPP24	0.40 - 0.60	(CI) Sandy CLAY	1.6
TPP27	0.40 - 0.55	(CH) Sandy CLAY	2.9
TPP29	0.60 - 0.95	(CI) Sandy CLAY	1.0

TABLE 4 – SUMMARY OF ATTERBERG LIMITS TESTING RESULTS

Location	Depth (m)	Material Description	Liquid Limit (%)	Plastic Limit (%)	Plasticity Index (%)	Linear Shrinkage (%)
Current Investigation						
BH501	0.80 – 1.00	FILL: (CL) Gravelly Sandy CLAY	23	18	5.0	1.0
BH504	0.50 – 0.70	FILL: (CL) Gravelly Sandy CLAY	30	14	16	7.0
BH505	0.50 – 0.65	FILL: (CL) Gravelly Sandy CLAY	30	17	13	5.0
BH511	0.40 – 0.50	FILL: (CI) Gravelly Sandy CLAY	35	15	20	9.0
Previous Investigation (Ref: NEW18P-0170B-AC, 4 March 2020)						
TPP22	1.20 – 1.30	(SC) Clayey SAND	29	16	13	5.0
TPP23	2.20 – 2.30	(CI) Sandy CLAY	30	14	16	7.0
TPP26	0.50 - 0.65	(CI) Gravelly Sandy CLAY	50	20	30	11.5
TPP28	0.60 - 0.70	(CI) Gravelly Sandy CLAY	36	19	17	7.0

The results of the Shrink/Swell and Atterberg Limits laboratory testing indicate that the residual soils tested from the site generally contain fines of medium to high plasticity.

6.0 Site Classification to AS2870-2011

Based on the results of the field work, laboratory testing and site regrade works conducted, residential lots located within Precinct 2, Stage 5 of the Brush Creek Estate residential subdivision, as shown on the attached Figure AC1, are classified in their current condition in accordance with AS2870-2011 *'Residential Slabs and Footings'*, as shown in Table 5.

TABLE 5 – SITE CLASSIFICATION TO AS2870-2011

Lot Numbers	Site Classification
506 to 509 and 515 to 520	**M**
501 to 505, 510 to 514 and 521 to 524	**H1**

A characteristic free surface movement of 20mm to 40mm is estimated for the lots classified as **Class 'M'** in their existing condition.

A characteristic free surface movement of 40mm to 60mm is estimated for the lots classified as **Class 'H1'** in their existing condition.

The effects of changes to the soil profile by additional cutting and filling and the effects of past and future trees should be considered in selection of the design value for differential movement.

If site re-grading works involving cutting or filling are performed after the date of this assessment, the classification may change and further advice should be sought.

Footings for the proposed development should be designed and constructed in accordance with the requirements of AS2870-2011.

The classification presented above assumes that:

- All footings are founded in controlled fill (if applicable) or in the residual clayey soils or rock below all non-controlled fill, topsoil material and root zones, and fill under slab panels meets the requirements of AS2870-2011, in particular, the root zone must be removed prior to the placement of fill materials beneath slabs;
- The performance expectations set out in Appendix B of AS2870-2011 are acceptable, and that site foundation maintenance is undertaken to avoid extremes of wetting and drying;
- Footings are to be founded outside of or below all zones of influence resulting from existing or future service trenches;
- The constructional and architectural requirements for reactive clay sites set out in AS2870-2011 are followed;
- Adherence to the detailing requirement outlined in Section 5 of AS2870-2011 '*Residential Slabs and Footings'* is essential, in particular Section 5.6, '*Additional requirements for Classes M, H1, H2 and E sites'* including architectural restrictions, plumbing and drainage requirements; and,
- Site maintenance complies with the provisions of CSIRO Sheet BTF 18, "*Foundation Maintenance and Footing Performance: A Homeowner's Guide*", a copy of which is attached in Appendix C.

All structural elements on all lots should be supported on footings founded beneath all uncontrolled fill, layers of inadequate bearing capacity, soft/loose, wet or other potentially deleterious material.

If any localised areas of uncontrolled fill of depths greater than 0.4m are encountered during construction, footings should be designed in accordance with engineering principles for Class 'P' sites.

7.0 Limitations

The findings presented in the report and used as the basis for recommendations presented herein were obtained using normal, industry accepted geotechnical design practices and standards. To our knowledge, they represent a reasonable interpretation of the general conditions of the site.

The extent of testing associated with this assessment is limited to discrete test locations. It should be noted that subsurface conditions between and away from the test locations may be different to those observed during the field work and used as the basis of the recommendations contained in this report.

If subsurface conditions encountered during construction differ from those given in this report, further advice should be sought without delay.

Data and opinions contained within the report may not be used in other contexts or for any other purposes without prior review and agreement by Qualtest. If this report is reproduced, it must be in full.

If you have any further questions regarding this report, please do not hesitate to contact Ben Edwards or the undersigned.

For and on behalf of Qualtest Laboratory (NSW) Pty Ltd.

Jason Lee
Principal Geotechnical Engineer

FIGURE AC1:

Site Plan and Approximate Test Locations



LEGEND:

- Approximate borehole location (Qualtest, 2021).
- Approximate extent of lot re-grade works (fill)
- Approximate test pit location (Qualtest, 2020).
- Approximate borehole location (Qualtest, 2018).

Based on drawing provided by client (REF: Project No: NE190257, Drawing No: C502.01, Issue: F, dated: 11.06.2020, by ACOR Consultants (NNSW) Pty Ltd).

Qualtest LABORATORY (NSW) PTY LTD

Client:	MCCLOY EDGEWORTH PTY LTD	Drawing No:	FIGURE AC1
Project:	BRUSH CREEK ESTATE - PRECINCT 2, STAGE 5	Project No:	NEW18P-0170B
Location:	OFF TRANSFIELD AVENUE, EDGEWORTH	Scale:	N.T.S.
Title:	SITE PLAN AND APPROXIMATE TEST LOCATIONS	Date:	19/01/2021

APPENDIX A:

Results of Field Investigations

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH501
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
AD/T	Not Encountered	0.80m D 1.00m		0.5 1.0 1.5 2.0		CI CH SP	FILL: TREE MULCH 0.10m FILL: Gravelly Sandy CLAY / Clayey SAND - low to medium plasticity, pale brown to brown, trace pale grey and orange, fine to coarse grained sand, fine to coarse grained (mostly fine to medium grained) angular to sub-angular gravel. 1.70m FILL: Sandy CLAY - medium to high plasticity, pale grey and pale orange-brown to orange, fine grained sand. 1.80m Gravelly SAND - fine to coarse grained, grey, fine to medium grained rounded to sub-rounded gravel. 2.00m Hole Terminated at 2.00 m	M M > w_P M	 VSt MD	 HP	 280	FILL - TREE MULCH FILL - CONTROLLED COLLUVIUM

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

BOREHOLE NO: BH502

CLIENT: McCLOY EDGEWORTH PTY LTD
PAGE: 1 OF 1
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
JOB NO: NEW18P-0170B
LOCATION: TRANSFIELD AVENUE, EDGEWORTH
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
SURFACE RL:
BOREHOLE DIAMETER: 300 mm
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
AD/T	Not Encountered	0.50m U50 0.70m		0.5 1.0 1.5 2.0		CL CH CH	FILL: TREE MULCH 0.10m FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel. 0.30m FILL: Gravelly Sandy CLAY - low to medium plasticity, pale brown to brown, trace pale grey and orange, fine to coarse grained sand, fine to coarse grained (mostly fine to medium grained) angular to sub-angular gravel. 1.60m CLAY - medium to high plasticity, pale grey with pale orange to orange, trace fine to coarse grained sand, trace fine to medium grained angular gravel. 2.00m Hole Terminated at 2.00 m	M M ~ w_P - M > w_P M > w_P	VSt - H VSt	HP HP HP HP HP HP	350 - 420 350 - 410 280 - 420 350 280 280	FILL - TREE MULCH FILL - TOPSOIL FILL - CONTROLLED RESIDUAL SOIL

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH503
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
AD/T	Not Encountered	1.20m U50 1.37m		0.5 1.0 1.5 2.0		CL CH CH	FILL: TREE MULCH 0.10m FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel. 0.30m FILL: Gravelly Sandy CLAY - low to medium plasticity, pale brown to brown, trace pale grey and orange, fine to coarse grained sand, fine to coarse grained (mostly fine to medium grained) angular to sub-angular gravel. 1.40m CLAY - medium to high plasticity, pale grey with pale orange to orange, trace fine to coarse grained sand, trace fine to medium grained angular gravel. 1.80m Hole Terminated at 1.80 m Refusal on weathered rock	M M ~ w_P - M > w_P M > w_P	VSt - H VSt	HP HP HP HP	320 - 480 350 - 450 280 280	FILL - TREE MULCH FILL - TOPSOIL FILL - CONTROLLED RESIDUAL SOIL

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH504
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		Structure and additional observations
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	
AD/T	Not Encountered						FILL: TREE MULCH					FILL - TREE MULCH
							0.10m					
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
							0.30m					
						CH	FILL: Gravelly Sandy CLAY - low to medium plasticity, pale brown to brown, trace pale grey and orange, fine to coarse grained sand, fine to coarse grained (mostly fine to medium grained) angular to sub-angular gravel.	M ~ w_P - M > w_P	VSt - H	HP	380 - 450	FILL - CONTROLLED
		0.50m		0.5								
		U50										
		0.70m										
										HP	360 - 450	
				1.0			1.00m					
						GP	FILL: Sandy GRAVEL - fine to coarse grained, angular to sub-angular, brown to pale brown, fine to coarse grained sand, with some fines of low to medium plasticity.	M	MD			
							1.30m					
						CH	Sandy CLAY - medium to high plasticity, pale grey and pale orange to orange, fine to coarse grained sand, trace fine to medium grained angular gravel.			HP	350	RESIDUAL SOIL / POSSIBLE CONTROLLED FILL
		1.50m		1.5			1.50m					
		U50					CLAY - medium to high plasticity, pale grey with pale orange to orange, trace fine to coarse grained sand, trace fine to medium grained angular gravel.	M > w_P	VSt	HP	280	RESIDUAL SOIL
		1.60m				CH						
										HP	280	
				2.0			2.00m					
							Hole Terminated at 2.00 m Refusal on weathered rock					

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

BOREHOLE NO: BH505

CLIENT: McCLOY EDGEWORTH PTY LTD
PAGE: 1 OF 1
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
JOB NO: NEW18P-0170B
LOCATION: TRANSFIELD AVENUE, EDGEWORTH
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
SURFACE RL:
BOREHOLE DIAMETER: 300 mm
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		Structure and additional observations
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	
							FILL: TREE MULCH					FILL - TREE MULCH
							0.10m					
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
							0.30m					
AD/T	Not Encountered	0.50m		0.5		CH	FILL: Gravelly Sandy CLAY - low to medium plasticity, pale brown to brown, trace pale grey and orange, fine to coarse grained sand, fine to coarse grained (mostly fine to medium grained) angular to sub-angular gravel.	M > w_P	VSt	HP	380	FILL - CONTROLLED
		U50 0.65m								HP	410	
								M < w_P	VSt - H	HP	450	
				1.0						HP	220	
										HP	220	
				1.5				M > w_P	VSt	HP	220	
							1.80m					
						CH	CLAY - medium to high plasticity, pale grey with pale orange to orange, trace fine to coarse grained sand, trace fine to medium grained angular gravel.			HP	280	RESIDUAL SOIL
				2.0			2.00m					
							Hole Terminated at 2.00 m					

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

BOREHOLE NO: BH506

CLIENT: McCLOY EDGEWORTH PTY LTD
PAGE: 1 OF 1
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
JOB NO: NEW18P-0170B
LOCATION: TRANSFIELD AVENUE, EDGEWORTH
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
SURFACE RL:
BOREHOLE DIAMETER: 300 mm
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
AD/T	Not Encountered	0.40m D 0.60m		0.5		CL	FILL: TREE MULCH 0.10m FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel. 0.40m	M				FILL - TREE MULCH FILL - TOPSOIL
						SC	Gravelly Clayey SAND - fine to coarse grained sand, pale grey and orange, fines of low plasticity, fine to coarse grained angular to sub-angular gravel. 0.60m		MD			RESIDUAL SOIL
							0.65m Sandy SILTSTONE - pale grey and pale orange to orange, estimated low to medium strength.	D				HIGHLY WEATHERED ROCK
				1.0			Hole Terminated at 0.65 m Practical Refusal					
				1.5								
				2.0								

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH507
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
AD/T	Not Encountered	0.40m U50 0.55m		0.5		CL	0.05m FILL: TREE MULCH					FILL - TREE MULCH
							FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
							0.20m CLAY - medium to high plasticity, pale orange with pale grey, trace fine to coarse grained sand, trace fine grained angular to sub-angular gravel.	M > w_P	VSt	HP	320	RESIDUAL SOIL
						CH				HP	300	
										HP	280	
				1.0			0.90m					
						CL	Silty CLAY - low to medium plasticity, pale grey and pale orange, with fine to coarse grained sand, trace fine to medium grained angular to sub-rounded gravel.	M < w_P	VSt - H	HP	380 - 450	RESIDUAL SOIL / EXTREMELY WEATHERED ROCK
							1.10m 1.15m Sandy SILTSTONE - pale grey and pale orange to orange, estimated low to medium strength.	D				HIGHLY WEATHERED ROCK
				1.5			Hole Terminated at 1.15 m Practical Refusal					
				2.0								

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH508
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		Structure and additional observations
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	
							FILL: TREE MULCH					FILL - TREE MULCH
							0.10m					
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
							0.30m					
AD/T	Not Encountered	0.50m U50 0.75m		0.5		CH	CLAY - medium to high plasticity, pale orange with pale grey, trace fine to coarse grained sand, trace fine grained angular to sub-angular gravel.	M > w_P	VSt	HP	280	RESIDUAL SOIL
				1.0						HP	320	
							1.10m					
						CL	Extremely Weathered Siltstone with soil properties: breaks down into Gravelly Sandy CLAY - low to medium plasticity, pale grey and pale orange, fine to coarse grained sand, fine to medium grained angular to sub-rounded gravel.	M < w_P	Fb			EXTREMELY WEATHERED ROCK / RESIDUAL SOIL
							1.40m 1.42m					
				1.5			Sandy SILTSTONE - pale grey and pale orange to orange, estimated low to medium strength.	D				HIGHLY WEATHERED ROCK
							Hole Terminated at 1.42 m Refusal					
				2.0								

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH509
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
AD/T	Not Encountered	0.30m U50 0.50m		0.5 1.0 1.5 2.0		CL CH CL	FILL: TREE MULCH 0.10m FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel. 0.30m CLAY - medium to high plasticity, pale orange with pale grey, trace fine to coarse grained sand, trace fine grained angular to sub-angular gravel. 0.50m Sandy CLAY - low to medium plasticity, pale grey and pale orange, fine to coarse grained sand, with fine to medium grained angular to sub-rounded gravel. 0.80m 0.82m Sandy SILTSTONE - pale grey and pale orange to orange, estimated low to medium strength. Hole Terminated at 0.82 m Refusal	M M > w_P D	VSt	HP HP	310 350	FILL - TREE MULCH FILL - TOPSOIL RESIDUAL SOIL HIGHLY WEATHERED ROCK

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

BOREHOLE NO: **BH510**

CLIENT: McCLOY EDGEWORTH PTY LTD
PAGE: 1 OF 1
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
JOB NO: NEW18P-0170B
LOCATION: TRANSFIELD AVENUE, EDGEWORTH
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
SURFACE RL:
BOREHOLE DIAMETER: 300 mm
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
							FILL: TREE MULCH					FILL - TREE MULCH
							0.10m					
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
							0.30m					
							FILL: Gravelly Sandy CLAY - medium plasticity, pale brown to brown, trace pale grey and orange, fine to coarse grained sand, fine to coarse grained (mostly fine to medium grained) angular to sub-angular gravel.					FILL - CONTROLLED
				0.5		CH			St - VSt	HP	220	
		0.70m										
		U50								HP	180 - 200	
		0.90m										
AD/T	Not Encountered						CLAY - medium to high plasticity, pale orange with pale grey, trace fine to coarse grained sand, trace fine grained angular to sub-angular gravel.					RESIDUAL SOIL
				1.0				M > w_P		HP	300	
							Increasing in sand content.					
										HP	220	
				1.5		CH			VSt	HP	280	
				2.0			2.00m					
							Hole Terminated at 2.00 m					

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH511
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
AD/T	Not Encountered						FILL: TREE MULCH					FILL - TREE MULCH
							0.10m					
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
							0.20m					
		0.40m					FILL: Gravelly Sandy CLAY - medium plasticity, pale brown to brown, trace pale grey and orange, fine to coarse grained sand, fine to coarse grained (mostly fine to medium grained) angular to sub-angular gravel.					FILL - CONTROLLED
		U50 0.50m		0.5		CH		M < w_P	VSt - H	HP	380 - 450	
										HP	480	
				1.0			1.00m					
							CLAY - medium to high plasticity, pale orange with pale grey, trace fine to coarse grained sand, trace fine grained angular to sub-angular gravel.					RESIDUAL SOIL
						CH		M > w_P	VSt	HP	350	
										HP	300	
				1.5						HP	320	
							1.70m					
						CL	Sandy CLAY / Clayey SAND - low to medium plasticity, pale orange with pale grey, fine to coarse grained sand.	D - M	Fb			RESIDUAL SOIL / EXTREMELY WEATHERED ROCK
				2.0			2.00m					
							Hole Terminated at 2.00 m					

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH512
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		Structure and additional observations
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	
AD/T	Not Encountered			0.0			FILL: TREE MULCH					FILL - TREE MULCH
							0.10m					
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
							0.30m					
							CLAY - medium to high plasticity, pale orange with pale grey, trace fine to coarse grained sand, trace fine grained angular to sub-angular gravel.					RESIDUAL SOIL
				0.5		CH		$M > w_P$	VSt	HP	350	
										HP	290	
				1.0			1.00m					
							Hole Terminated at 1.00 m					
				1.5								
				2.0								

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH513
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
							FILL: TREE MULCH					FILL - TREE MULCH
							0.10m					
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
							0.30m					
						SP	FILL: SAND - fine to coarse grained, pale grey.					FILL
							0.40m			HP	280	
AD/T	Not Encountered	0.50m		0.5		CH	CLAY - medium to high plasticity, pale orange with pale grey, trace fine to coarse grained sand, trace fine grained angular to sub-angular gravel.	M > w_P	VSt	HP	280	RESIDUAL SOIL
		U50										
		0.70m								HP	300	
				1.0			1.00m					
						CL	Sandy CLAY / Clayey SAND - low plasticity, low plasticity, pale orange with pale grey, fine to medium grained sand.					RESIDUAL SOIL / EXTREMELY WEATHERED ROCK
							1.10m					
							Hole Terminated at 1.10 m Refusal on weathered rock					
				1.5								
				2.0								

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Moisture Condition	
D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

Density		
V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH515
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		Structure and additional observations
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	
							FILL: TREE MULCH					FILL - TREE MULCH
							0.10m					
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
							0.30m					
AD/T	Not Encountered	0.40m					CLAY - medium to high plasticity, pale orange with pale grey, trace fine to coarse grained sand, trace fine grained angular to sub-angular gravel.					RESIDUAL SOIL
		U50		0.5						HP	320	
		0.55m				CH		M > w_P	VSt	HP	300	
										HP	280	
							0.90m					
							0.92m	D				
							Sandy SILTSTONE - pale grey and pale orange to orange, estimated low to medium strength.					HIGHLY WEATHERED ROCK
				1.0			Hole Terminated at 0.92 m Refusal					
				1.5								
				2.0								

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density		
V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition	
D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH516
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		Structure and additional observations
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	
AD/T	Not Encountered	0.30m U50 0.50m		0.5		CL CH	FILL: TREE MULCH 0.10m FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel. 0.20m CLAY - medium to high plasticity, pale orange with pale grey, trace fine to coarse grained sand, trace fine grained angular to sub-angular gravel.	M M > w_P	St - VSt	HP HP	210 230	FILL - TREE MULCH FILL - TOPSOIL RESIDUAL SOIL
							0.60m 0.62m Sandy SILTSTONE - pale grey and pale orange to orange, estimated low to medium strength. Hole Terminated at 0.62 m Refusal	D				HIGHLY WEATHERED ROCK
				1.0								
				1.5								
				2.0								

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density		
V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition	
D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH517
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
AD/T	Not Encountered	0.30m U50 0.45m		0.5		CL CH	FILL: TREE MULCH 0.10m FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel. 0.25m CLAY - medium to high plasticity, pale orange with pale grey, trace fine to coarse grained sand, trace fine grained angular to sub-angular gravel. 0.50m 0.52m Sandy SILTSTONE - pale grey and pale orange to orange, estimated low to medium strength. Hole Terminated at 0.52 m Practical Refusal	M M > w_P D	VSt	HP HP	230 360	FILL - TREE MULCH FILL - TOPSOIL RESIDUAL SOIL HIGHLY WEATHERED ROCK

1.0
1.5
2.0

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Moisture Condition	
D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

Density		
V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

BOREHOLE NO: BH518

CLIENT: McCLOY EDGEWORTH PTY LTD

PAGE: 1 OF 1

PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5

JOB NO: NEW18P-0170B

LOCATION: TRANSFIELD AVENUE, EDGEWORTH

LOGGED BY: BE

DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER

SURFACE RL:

BOREHOLE DIAMETER: 300 mm

DATUM:

Drilling and Sampling					Material description and profile information					Field Test		Structure and additional observations
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	
AD/T	Not Encountered						FILL: TREE MULCH					FILL - TREE MULCH
							0.10m FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
						CL	0.40m					
							0.45m Sandy SILTSTONE - pale grey and pale orange to orange, estimated low to medium strength, trace extremely weathered pockets.	D				HIGHLY WEATHERED ROCK
				0.5			Hole Terminated at 0.45 m Practical Refusal					
				1.0								
				1.5								
				2.0								

LEGEND:

Water

- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes

- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Moisture Condition	
D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

Density		
V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:55 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH519
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
AD/T	Not Encountered	0.30m D 0.40m		0.5 1.0 1.5 2.0		CL CL	0.05m FILL: TREE MULCH FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel. 0.30m Extremely Weathered Siltstone with soil properties: breaks down into Gravelly Sandy CLAY - low to medium plasticity, pale grey and pale orange, fine to coarse grained sand, fine to medium grained angular to sub-rounded gravel. 0.40m 0.45m Sandy SILTSTONE - pale grey and pale orange to orange, estimated low to medium strength. Hole Terminated at 0.45 m Practical Refusal	M M ~ w_p D	VSt - H	HP	380 - 450	FILL - TREE MULCH FILL - TOPSOIL EXTREMELY WEATHERED ROCK / RESIDUAL SOIL HIGHLY WEATHERED ROCK

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:56 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH520
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		Structure and additional observations
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	
AD/T	Not Encountered						FILL: TREE MULCH					FILL - TREE MULCH
							0.10m	M				
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.					FILL - TOPSOIL
							0.20m					
						CH	FILL: Sandy CLAY - medium to high plasticity, grey to brown and orange, fine to coarse grained sand.	M > w_P	St	HP	180	FILL / POSSIBLE RESIDUAL SOIL
							0.30m					
						CH	CLAY - medium to high plasticity, pale orange and pale grey, trace fine to coarse grained sand, trace fine to medium grained angular gravel.		VSt	HP	280	RESIDUAL SOIL
							0.40m					
							0.42m	D				HIGHLY WEATHERED ROCK
				0.5			Sandy SILTSTONE - pale grey and pale orange to orange, estimated low to medium strength.					
							Hole Terminated at 0.42 m Practical Refusal					
				1.0								
				1.5								
				2.0								

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Moisture Condition	
D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

Density		
V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:56 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH521
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
AD/T	Not Encountered	0.50m U50 0.65m		0.5 1.0 1.5 2.0		CL CI CH	FILL: TREE MULCH 0.10m FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel. 0.20m FILL: Gravelly Sandy CLAY - medium plasticity, pale brown to brown, trace pale grey and orange, fine to coarse grained sand, fine to coarse grained (mostly fine to medium grained) angular to sub-angular gravel. 0.80m CLAY - medium to high plasticity, pale grey with pale orange to orange, trace fine to coarse grained sand, trace fine to medium grained angular gravel. Pale grey-white with orange to red-brown. 1.80m Hole Terminated at 1.80 m Refusal on weathered rock	M M > w_P	St VSt	HP HP HP HP HP HP	180 180 150 320 240 250 380	FILL - TREE MULCH FILL - TOPSOIL FILL - CONTROLLED RESIDUAL SOIL

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density		
V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition	
D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:56 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH522
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		Structure and additional observations
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	
							FILL: TREE MULCH					FILL - TREE MULCH
							0.10m					
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
							0.20m					
						CH	FILL: Sandy CLAY - medium plasticity, grey to brown and orange, fine to coarse grained sand.	M < w_P	VSt - H	HP	480	FILL - CONTROLLED
							0.40m					
							CLAY - medium to high plasticity, pale orange and pale grey, trace fine to coarse grained sand, trace fine to medium grained angular gravel.					RESIDUAL SOIL
				0.5						HP	380	
AD/T	Not Encountered	0.80m				CH		M > w_P	VSt			
		U50								HP	300	
		1.00m		1.0								
							Pale grey-white with some orange to red-brown.			HP	220	
							1.30m					
							1.35m Sandy SILTSTONE - pale grey and pale orange to orange, estimated low to medium strength.	D				HIGHLY WEATHERED ROCK
							Hole Terminated at 1.35 m Refusal					
				1.5								
				2.0								

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:56 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH523
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
AD/T	Not Encountered						FILL: TREE MULCH					FILL - TREE MULCH
							0.10m	M				
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.					FILL - TOPSOIL
							0.20m					FILL - CONTROLLED
						CH	FILL: Gravelly CLAY - medium plasticity, grey and brown, fine to medium grained sub-angular to sub-rounded gravel, with some fine to coarse grained sand.			HP	280 - 350	
				0.5								
							0.60m					RESIDUAL SOIL
							CLAY - medium to high plasticity, pale orange and pale grey, trace fine to coarse grained sand, trace fine to medium grained angular gravel.			HP	380	
		1.00m						M > w_P	VSt			
		U50 1.15m		1.0			Pale grey-white with some orange to red-brown.			HP	320	
						CH						
				1.5						HP	320	
							1.70m					RESIDUAL SOIL / EXTREMELY WEATHERED ROCK
						CL	Sandy CLAY / Clayey SAND - low to medium plasticity, pale orange with pale grey, fine to coarse grained sand.	M < w_P	Fb			
							1.90m					HIGHLY WEATHERED ROCK
				2.0			Sandy SILTSTONE - pale grey and pale orange to orange, estimated very low to low strength. 2.00m	D				
							Hole Terminated at 2.00 m Practical Refusal					

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:56 10.0.000 Datgel Lab and In Situ Tool

ENGINEERING LOG - BOREHOLE

CLIENT: McCLOY EDGEWORTH PTY LTD
PROJECT: BRUSH CREEK SUBDIVISION - STAGE 5
LOCATION: TRANSFIELD AVENUE, EDGEWORTH

BOREHOLE NO: BH524
PAGE: 1 OF 1
JOB NO: NEW18P-0170B
LOGGED BY: BE
DATE: 5/1/21

DRILL TYPE: 2.7 TONNE EXCAVATOR WITH AUGER
BOREHOLE DIAMETER: 300 mm
SURFACE RL:
DATUM:

Drilling and Sampling					Material description and profile information					Field Test		
METHOD	WATER	SAMPLES	RL (m)	DEPTH (m)	GRAPHIC LOG	CLASSIFICATION SYMBOL	MATERIAL DESCRIPTION: Soil type, plasticity/particle characteristics,colour,minor components	MOISTURE CONDITION	CONSISTENCY DENSITY	Test Type	Result	Structure and additional observations
							0.05m FILL: TREE MULCH					FILL - TREE MULCH
						CL	FILL-TOPSOIL: Gravelly Sandy CLAY - low plasticity, dark grey, fine to coarse grained sand, fine to medium grained angular to sub-angular gravel.	M				FILL - TOPSOIL
							0.30m CLAY - medium plasticity, pale orange and pale grey, trace fine to coarse grained sand, trace fine to medium grained angular gravel.			HP	360	RESIDUAL SOIL
AD/T	Not Encountered	0.50m U50 0.65m		0.5		CH		M > w_P	VSt	HP	380	
										HP	380	
				1.0						HP	280	
							1.30m Sandy CLAY / Clayey SAND - low to medium plasticity, pale orange with pale grey, fine to coarse grained sand.	M < w_P	Fb			RESIDUAL SOIL / EXTREMELY WEATHERED ROCK
				1.5		CL	1.50m					
							Hole Terminated at 1.50 m Refusal on weathered rock					
				2.0								

LEGEND:

Water
- Water Level (Date and time shown)
- Water Inflow
- Water Outflow

Strata Changes
- Gradational or transitional strata
- Definitive or distict strata change

Notes, Samples and Tests

U_{50}	50mm Diameter tube sample
CBR	Bulk sample for CBR testing
E	Environmental sample (Glass jar, sealed and chilled on site)
ASS	Acid Sulfate Soil Sample (Plastic bag, air expelled, chilled)
B	Bulk Sample

Field Tests

PID	Photoionisation detector reading (ppm)
DCP(x-y)	Dynamic penetrometer test (test depth interval shown)
HP	Hand Penetrometer test (UCS kPa)

Consistency

		UCS (kPa)
VS	Very Soft	<25
S	Soft	25 - 50
F	Firm	50 - 100
St	Stiff	100 - 200
VSt	Very Stiff	200 - 400
H	Hard	>400
Fb	Friable	

Density

V	Very Loose	Density Index <15%
L	Loose	Density Index 15 - 35%
MD	Medium Dense	Density Index 35 - 65%
D	Dense	Density Index 65 - 85%
VD	Very Dense	Density Index 85 - 100%

Moisture Condition

D	Dry
M	Moist
W	Wet
W_p	Plastic Limit
W_L	Liquid Limit

QT LIB 1.1.GLB Log NON-CORED BOREHOLE - TEST PIT NEW18P-0170B DRAFT LOGS.GPJ <<DrawingFile>> 19/01/2021 12:56 10.0.000 Datgel Lab and In Situ Tool

APPENDIX B:

Results of Laboratory Testing

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: SSI:NEW21W-0008-S02
Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S02	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH502 - (0.5 - 0.7m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-0.6
Moisture Content before (%):	14.1
Moisture Content after (%):	21.7
Est. Unc. Comp. Strength before (kPa):	>600
Est. Unc. Comp. Strength after (kPa):	220

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	1.2
Shrinkage Moisture Content (%):	16.7
Est. inert material (%):	8%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 0.7

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: SSI:NEW21W-0008-S03
Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S03	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH503 - (1.2 - 1.37m)		
Date Tested:	6/01/2021		

Swell Test AS 1289.7.1.1

Swell on Saturation (%):	-0.1
Moisture Content before (%):	17.8
Moisture Content after (%):	21.6
Est. Unc. Comp. Strength before (kPa):	300
Est. Unc. Comp. Strength after (kPa):	200

Shrink Test AS 1289.7.1.1

Shrink on drying (%):	1.4
Shrinkage Moisture Content (%):	13.6
Est. inert material (%):	7%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Moderate

Shrink Swell



Shrink Swell Index - Iss (%): 0.8

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: SSI:NEW21W-0008-S05
Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S05	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH504 - (1.5 - 1.6m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-0.5
Moisture Content before (%):	25.9
Moisture Content after (%):	30.9
Est. Unc. Comp. Strength before (kPa):	290
Est. Unc. Comp. Strength after (kPa):	200

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	4.2
Shrinkage Moisture Content (%):	26.7
Est. inert material (%):	4%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Major

Shrink Swell



Shrink Swell Index - Iss (%): 2.3

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Shrink Swell Index Report

Report No: SSI:NEW21W-0008-S07
Issue No: 1

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S07	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH507 - (0.4 - 0.55m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-0.1
Moisture Content before (%):	26.0
Moisture Content after (%):	29.4
Est. Unc. Comp. Strength before (kPa):	480
Est. Unc. Comp. Strength after (kPa):	390

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	5.5
Shrinkage Moisture Content (%):	25.7
Est. inert material (%):	2%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 3.0

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: SSI:NEW21W-0008-S08
Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S08	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH508 - (0.5 - 0.75m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-0.4
Moisture Content before (%):	23.0
Moisture Content after (%):	26.7
Est. Unc. Comp. Strength before (kPa):	350
Est. Unc. Comp. Strength after (kPa):	150

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	3.2
Shrinkage Moisture Content (%):	21.2
Est. inert material (%):	2%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 1.8

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: SSI:NEW21W-0008-S09
Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S09	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH509 - (0.3 - 0.5m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-0.6
Moisture Content before (%):	22.1
Moisture Content after (%):	24.6
Est. Unc. Comp. Strength before (kPa):	350
Est. Unc. Comp. Strength after (kPa):	390

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	4.0
Shrinkage Moisture Content (%):	22.3
Est. inert material (%):	6%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Moderate

Shrink Swell



Shrink Swell Index - Iss (%): 2.2

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: SSI:NEW21W-0008-S10
Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S10	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH510 - (0.7 - 0.9m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-0.7
Moisture Content before (%):	28.8
Moisture Content after (%):	31.4
Est. Unc. Comp. Strength before (kPa):	410
Est. Unc. Comp. Strength after (kPa):	250

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	4.9
Shrinkage Moisture Content (%):	29.1
Est. inert material (%):	4%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Minor

Shrink Swell



Shrink Swell Index - Iss (%): 2.7

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: SSI:NEW21W-0008-S12
Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S12	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH513 - (0.5 - 0.7m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-0.7
Moisture Content before (%):	24.4
Moisture Content after (%):	27.4
Est. Unc. Comp. Strength before (kPa):	530
Est. Unc. Comp. Strength after (kPa):	400

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	2.8
Shrinkage Moisture Content (%):	25.1
Est. inert material (%):	4%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 1.5

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Shrink Swell Index Report

Report No: SSI:NEW21W-0008-S13
Issue No: 1

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S13	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH515 - (0.4 - 0.55m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-0.6
Moisture Content before (%):	26.1
Moisture Content after (%):	29.2
Est. Unc. Comp. Strength before (kPa):	250
Est. Unc. Comp. Strength after (kPa):	230

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	4.8
Shrinkage Moisture Content (%):	25.6
Est. inert material (%):	3%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 2.7

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: SSI:NEW21W-0008-S14
Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S14	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH521 - (0.5 - 0.65m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-0.6
Moisture Content before (%):	17.1
Moisture Content after (%):	23.8
Est. Unc. Comp. Strength before (kPa):	150
Est. Unc. Comp. Strength after (kPa):	160

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	1.3
Shrinkage Moisture Content (%):	14.5
Est. inert material (%):	5%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 0.7

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: SSI:NEW21W-0008-S15
Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S15	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH522 - (0.8 - 0.1.0m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-0.4
Moisture Content before (%):	21.1
Moisture Content after (%):	27.7
Est. Unc. Comp. Strength before (kPa):	410
Est. Unc. Comp. Strength after (kPa):	350

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	2.6
Shrinkage Moisture Content (%):	22.3
Est. inert material (%):	6%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Major

Shrink Swell



Shrink Swell Index - Iss (%): 1.4

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: SSI:NEW21W-0008-S16
Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S16	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH523 - (1.0 - 1.15m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-0.4
Moisture Content before (%):	23.9
Moisture Content after (%):	26.7
Est. Unc. Comp. Strength before (kPa):	560
Est. Unc. Comp. Strength after (kPa):	470

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	3.3
Shrinkage Moisture Content (%):	23.9
Est. inert material (%):	2%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 1.8

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: SSI:NEW21W-0008-S17
Issue No: 1

Shrink Swell Index Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID:	NEW21W-0008-S17	**Sampling Method:**	Sampled by Engineering Department
Material:	Insitu	**Date Sampled:**	5/01/2021
Source:	On-Site	**Date Submitted:**	6/01/2021
Specification:	No Specification		
Project Location:	Transfield Avenue, Edgeworth		
Sample Location:	BH524 - (0.5 - 0.65m)		
Date Tested:	6/01/2021		

Swell Test — AS 1289.7.1.1

Swell on Saturation (%):	-1.0
Moisture Content before (%):	26.5
Moisture Content after (%):	30.7
Est. Unc. Comp. Strength before (kPa):	590
Est. Unc. Comp. Strength after (kPa):	400

Shrink Test — AS 1289.7.1.1

Shrink on drying (%):	3.3
Shrinkage Moisture Content (%):	27.1
Est. inert material (%):	1%
Crumbling during shrinkage:	Nil
Cracking during shrinkage:	Nil

Shrink Swell



Shrink Swell Index - Iss (%): 1.8

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Material Test Report

Report No: MAT:NEW21W-0008-S01
Issue No: 1

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 18/01/2021

Sample Details

Sample ID: NEW21W-0008-S01
Sampling Method: Sampled by Engineering Department
Date Sampled: 05/01/2021
Source: On-Site
Material: Insitu
Specification: No Specification
Project Location: Transfield Avenue, Edgeworth
Sample Location: BH501 - (0.8 - 1.0m)

Test Results

Description	Method	Result	Limits
Sample History	AS 1289.1.1	Oven-dried	
Preparation	AS 1289.1.1	Dry Sieved	
Linear Shrinkage (%)	AS 1289.3.4.1	1.0	
Mould Length (mm)		250	
Crumbling		No	
Curling		No	
Cracking		Yes	
Liquid Limit (%)	AS 1289.3.1.1	23	
Method		Four Point	
Plastic Limit (%)	AS 1289.3.2.1	18	
Plasticity Index (%)	AS 1289.3.3.1	5	
Date Tested		8/01/2021	

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: MAT:NEW21W-0008-S04
Issue No: 1

Material Test Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID: NEW21W-0008-S04
Sampling Method: Sampled by Engineering Department
Date Sampled: 05/01/2021
Source: On-Site
Material: Insitu
Specification: No Specification
Project Location: Transfield Avenue, Edgeworth
Sample Location: BH504 - (0.5 - 0.7m)

Test Results

Description	Method	Result	Limits
Sample History	AS 1289.1.1	Oven-dried	
Preparation	AS 1289.1.1	Dry Sieved	
Linear Shrinkage (%)	AS 1289.3.4.1	7.0	
Mould Length (mm)		250	
Crumbling		No	
Curling		No	
Cracking		No	
Liquid Limit (%)	AS 1289.3.1.1	30	
Method		Four Point	
Plastic Limit (%)	AS 1289.3.2.1	14	
Plasticity Index (%)	AS 1289.3.3.1	16	
Date Tested		8/01/2021	

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: MAT:NEW21W-0008-S06
Issue No: 1

Material Test Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Brent Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 12/01/2021

Sample Details

Sample ID: NEW21W-0008-S06
Sampling Method: Sampled by Engineering Department
Date Sampled: 05/01/2021
Source: On-Site
Material: Insitu
Specification: No Specification
Project Location: Transfield Avenue, Edgeworth
Sample Location: BH505 - (0.5 - 0.65m)

Test Results

Description	Method	Result	Limits
Sample History	AS 1289.1.1	Oven-dried	
Preparation	AS 1289.1.1	Dry Sieved	
Linear Shrinkage (%)	AS 1289.3.4.1	5.0	
Mould Length (mm)		250	
Crumbling		No	
Curling		No	
Cracking		Yes	
Liquid Limit (%)	AS 1289.3.1.1	30	
Method		Four Point	
Plastic Limit (%)	AS 1289.3.2.1	17	
Plasticity Index (%)	AS 1289.3.3.1	13	
Date Tested		11/01/2021	

Comments

The results outlined above apply to the sample as received

© 2000-2021 QESTLab by SpectraQEST.com

QUALTEST Laboratory (NSW) Pty Ltd (20708)
8 Ironbark Close Warabrook NSW 2304
T: 02 4968 4468
F: 02 4960 9775
E: admin@qualtest.com.au
W: www.qualtest.com.au
ABN: 98 153 268 896

Report No: MAT:NEW21W-0008-S11
Issue No: 1

Material Test Report

Client: McCloy Project Management Pty Ltd
PO Box 2214
Dangar NSW 2309

Project No.: NEW18P-0170B
Project Name: Brush Creek Subdivision - Precinct 2, Stage 5

Accredited for compliance with ISO/IEC 17025-Testing.
The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.
Results provided relate only to the items tested or sampled.

Approved Signatory: Dane Cullen
(Senior Geotechnician)
NATA Accredited Laboratory Number: 18686
Date of Issue: 13/01/2021

Sample Details

Sample ID: NEW21W-0008-S11
Sampling Method: Sampled by Engineering Department
Date Sampled: 05/01/2021
Source: On-Site
Material: Insitu
Specification: No Specification
Project Location: Transfield Avenue, Edgeworth
Sample Location: BH511 - (0.4 - 0.5m)

Test Results

Description	Method	Result	Limits
Sample History	AS 1289.1.1	Oven-dried	
Preparation	AS 1289.1.1	Dry Sieved	
Linear Shrinkage (%)	AS 1289.3.4.1	9.0	
Mould Length (mm)		250	
Crumbling		No	
Curling		No	
Cracking		No	
Liquid Limit (%)	AS 1289.3.1.1	35	
Method		Four Point	
Plastic Limit (%)	AS 1289.3.2.1	15	
Plasticity Index (%)	AS 1289.3.3.1	20	
Date Tested		12/01/2021	

Comments

N/A

© 2000-2021 QESTLab by SpectraQEST.com

APPENDIX C:

CSIRO Sheet BTF 18

Foundation Maintenance and Footing Performance: A Homeowner's Guide

Foundation Maintenance and Footing Performance:
A Homeowner's Guide

CSIRO

BTF 18 replaces Information Sheet 10/91

Buildings can and often do move. This movement can be up, down, lateral or rotational. The fundamental cause of movement in buildings can usually be related to one or more problems in the foundation soil. It is important for the homeowner to identify the soil type in order to ascertain the measures that should be put in place in order to ensure that problems in the foundation soil can be prevented, thus protecting against building movement.

This Building Technology File is designed to identify causes of soil-related building movement, and to suggest methods of prevention of resultant cracking in buildings.

Soil Types

The types of soils usually present under the topsoil in land zoned for residential buildings can be split into two approximate groups – granular and clay. Quite often, foundation soil is a mixture of both types. The general problems associated with soils having granular content are usually caused by erosion. Clay soils are subject to saturation and swell/shrink problems.

Classifications for a given area can generally be obtained by application to the local authority, but these are sometimes unreliable and if there is doubt, a geotechnical report should be commissioned. As most buildings suffering movement problems are founded on clay soils, there is an emphasis on classification of soils according to the amount of swell and shrinkage they experience with variations of water content. The table below is Table 2.1 from AS 2870, the Residential Slab and Footing Code.

Causes of Movement

Settlement due to construction
There are two types of settlement that occur as a result of construction:

- Immediate settlement occurs when a building is first placed on its foundation soil, as a result of compaction of the soil under the weight of the structure. The cohesive quality of clay soil mitigates against this, but granular (particularly sandy) soil is susceptible.
- Consolidation settlement is a feature of clay soil and may take place because of the expulsion of moisture from the soil or because of the soil's lack of resistance to local compressive or shear stresses. This will usually take place during the first few months after construction, but has been known to take many years in exceptional cases.

These problems are the province of the builder and should be taken into consideration as part of the preparation of the site for construction. Building Technology File 19 (BTF 19) deals with these problems.

Erosion
All soils are prone to erosion, but sandy soil is particularly susceptible to being washed away. Even clay with a sand component of say 10% or more can suffer from erosion.

Saturation
This is particularly a problem in clay soils. Saturation creates a bog-like suspension of the soil that causes it to lose virtually all of its bearing capacity. To a lesser degree, sand is affected by saturation because saturated sand may undergo a reduction in volume – particularly imported sand fill for bedding and blinding layers. However, this usually occurs as immediate settlement and should normally be the province of the builder.

Seasonal swelling and shrinkage of soil
All clays react to the presence of water by slowly absorbing it, making the soil increase in volume (see table below). The degree of increase varies considerably between different clays, as does the degree of decrease during the subsequent drying out caused by fair weather periods. Because of the low absorption and expulsion rate, this phenomenon will not usually be noticeable unless there are prolonged rainy or dry periods, usually of weeks or months, depending on the land and soil characteristics.

The swelling of soil creates an upward force on the footings of the building, and shrinkage creates subsidence that takes away the support needed by the footing to retain equilibrium.

Shear failure
This phenomenon occurs when the foundation soil does not have sufficient strength to support the weight of the footing. There are two major post-construction causes:

- Significant load increase.
- Reduction of lateral support of the soil under the footing due to erosion or excavation.
- In clay soil, shear failure can be caused by saturation of the soil adjacent to or under the footing.

GENERAL DEFINITIONS OF SITE CLASSES

Class	Foundation
A	Most sand and rock sites with little or no ground movement from moisture changes
S	Slightly reactive clay sites with only slight ground movement from moisture changes
M	Moderately reactive clay or silt sites, which can experience moderate ground movement from moisture changes
H	Highly reactive clay sites, which can experience high ground movement from moisture changes
E	Extremely reactive sites, which can experience extreme ground movement from moisture changes
A to P	Filled sites
P	Sites which include soft soils, such as soft clay or silt or loose sands; landslip; mine subsidence; collapsing soils; soils subject to erosion; reactive sites subject to abnormal moisture conditions or sites which cannot be classified otherwise

Tree root growth

Trees and shrubs that are allowed to grow in the vicinity of footings can cause foundation soil movement in two ways:

- Roots that grow under footings may increase in cross-sectional size, exerting upward pressure on footings.
- Roots in the vicinity of footings will absorb much of the moisture in the foundation soil, causing shrinkage or subsidence.

Unevenness of Movement

The types of ground movement described above usually occur unevenly throughout the building's foundation soil. Settlement due to construction tends to be uneven because of:

- Differing compaction of foundation soil prior to construction.
- Differing moisture content of foundation soil prior to construction.

Movement due to non-construction causes is usually more uneven still. Erosion can undermine a footing that traverses the flow or can create the conditions for shear failure by eroding soil adjacent to a footing that runs in the same direction as the flow.

Saturation of clay foundation soil may occur where subfloor walls create a dam that makes water pond. It can also occur wherever there is a source of water near footings in clay soil. This leads to a severe reduction in the strength of the soil which may create local shear failure.

Seasonal swelling and shrinkage of clay soil affects the perimeter of the building first, then gradually spreads to the interior. The swelling process will usually begin at the uphill extreme of the building, or on the weather side where the land is flat. Swelling gradually reaches the interior soil as absorption continues. Shrinkage usually begins where the sun's heat is greatest.

Effects of Uneven Soil Movement on Structures

Erosion and saturation

Erosion removes the support from under footings, tending to create subsidence of the part of the structure under which it occurs. Brickwork walls will resist the stress created by this removal of support by bridging the gap or cantilevering until the bricks or the mortar bedding fail. Older masonry has little resistance. Evidence of failure varies according to circumstances and symptoms may include:

- Step cracking in the mortar beds in the body of the wall or above/below openings such as doors or windows.
- Vertical cracking in the bricks (usually but not necessarily in line with the vertical beds or perpends).

Isolated piers affected by erosion or saturation of foundations will eventually lose contact with the bearers they support and may tilt or fall over. The floors that have lost this support will become bouncy, sometimes rattling ornaments etc.

Seasonal swelling/shrinkage in clay

Swelling foundation soil due to rainy periods first lifts the most exposed extremities of the footing system, then the remainder of the perimeter footings while gradually permeating inside the building footprint to lift internal footings. This swelling first tends to create a dish effect, because the external footings are pushed higher than the internal ones.

The first noticeable symptom may be that the floor appears slightly dished. This is often accompanied by some doors binding on the floor or the door head, together with some cracking of cornice mitres. In buildings with timber flooring supported by bearers and joists, the floor can be bouncy. Externally there may be visible dishing of the hip or ridge lines.

As the moisture absorption process completes its journey to the innermost areas of the building, the internal footings will rise. If the spread of moisture is roughly even, it may be that the symptoms will temporarily disappear, but it is more likely that swelling will be uneven, creating a difference rather than a disappearance in symptoms. In buildings with timber flooring supported by bearers and joists, the isolated piers will rise more easily than the strip footings or piers under walls, creating noticeable doming of flooring.

Trees can cause shrinkage and damage



As the weather pattern changes and the soil begins to dry out, the external footings will be first affected, beginning with the locations where the sun's effect is strongest. This has the effect of lowering the external footings. The doming is accentuated and cracking reduces or disappears where it occurred because of dishing, but other cracks open up. The roof lines may become convex.

Doming and dishing are also affected by weather in other ways. In areas where warm, wet summers and cooler dry winters prevail, water migration tends to be toward the interior and doming will be accentuated, whereas where summers are dry and winters are cold and wet, migration tends to be toward the exterior and the underlying propensity is toward dishing.

Movement caused by tree roots

In general, growing roots will exert an upward pressure on footings, whereas soil subject to drying because of tree or shrub roots will tend to remove support from under footings by inducing shrinkage.

Complications caused by the structure itself

Most forces that the soil causes to be exerted on structures are vertical – i.e. either up or down. However, because these forces are seldom spread evenly around the footings, and because the building resists uneven movement because of its rigidity, forces are exerted from one part of the building to another. The net result of all these forces is usually rotational. This resultant force often complicates the diagnosis because the visible symptoms do not simply reflect the original cause. A common symptom is binding of doors on the vertical member of the frame.

Effects on full masonry structures

Brickwork will resist cracking where it can. It will attempt to span areas that lose support because of subsided foundations or raised points. It is therefore usual to see cracking at weak points, such as openings for windows or doors.

In the event of construction settlement, cracking will usually remain unchanged after the process of settlement has ceased.

With local shear or erosion, cracking will usually continue to develop until the original cause has been remedied, or until the subsidence has completely neutralised the affected portion of footing and the structure has stabilised on other footings that remain effective.

In the case of swell/shrink effects, the brickwork will in some cases return to its original position after completion of a cycle, however it is more likely that the rotational effect will not be exactly reversed, and it is also usual that brickwork will settle in its new position and will resist the forces trying to return it to its original position. This means that in a case where swelling takes place after construction and cracking occurs, the cracking is likely to at least partly remain after the shrink segment of the cycle is complete. Thus, each time the cycle is repeated, the likelihood is that the cracking will become wider until the sections of brickwork become virtually independent.

With repeated cycles, once the cracking is established, if there is no other complication, it is normal for the incidence of cracking to stabilise, as the building has the articulation it needs to cope with the problem. This is by no means always the case, however, and monitoring of cracks in walls and floors should always be treated seriously.

Upheaval caused by growth of tree roots under footings is not a simple vertical shear stress. There is a tendency for the root to also exert lateral forces that attempt to separate sections of brickwork after initial cracking has occurred.

The normal structural arrangement is that the inner leaf of brickwork in the external walls and at least some of the internal walls (depending on the roof type) comprise the load-bearing structure on which any upper floors, ceilings and the roof are supported. In these cases, it is internally visible cracking that should be the main focus of attention, however there are a few examples of dwellings whose external leaf of masonry plays some supporting role, so this should be checked if there is any doubt. In any case, externally visible cracking is important as a guide to stresses on the structure generally, and it should also be remembered that the external walls must be capable of supporting themselves.

Effects on framed structures
Timber or steel framed buildings are less likely to exhibit cracking due to swell/shrink than masonry buildings because of their flexibility. Also, the doming/dishing effects tend to be lower because of the lighter weight of walls. The main risks to framed buildings are encountered because of the isolated pier footings used under walls. Where erosion or saturation cause a footing to fall away, this can double the span which a wall must bridge. This additional stress can create cracking in wall linings, particularly where there is a weak point in the structure caused by a door or window opening. It is, however, unlikely that framed structures will be so stressed as to suffer serious damage without first exhibiting some or all of the above symptoms for a considerable period. The same warning period should apply in the case of upheaval. It should be noted, however, that where framed buildings are supported by strip footings there is only one leaf of brickwork and therefore the externally visible walls are the supporting structure for the building. In this case, the subfloor masonry walls can be expected to behave as full brickwork walls.

Effects on brick veneer structures
Because the load-bearing structure of a brick veneer building is the frame that makes up the interior leaf of the external walls plus perhaps the internal walls, depending on the type of roof, the building can be expected to behave as a framed structure, except that the external masonry will behave in a similar way to the external leaf of a full masonry structure.

Water Service and Drainage

Where a water service pipe, a sewer or stormwater drainage pipe is in the vicinity of a building, a water leak can cause erosion, swelling or saturation of susceptible soil. Even a minuscule leak can be enough to saturate a clay foundation. A leaking tap near a building can have the same effect. In addition, trenches containing pipes can become watercourses even though backfilled, particularly where broken rubble is used as fill. Water that runs along these trenches can be responsible for serious erosion, interstrata seepage into subfloor areas and saturation.

Pipe leakage and trench water flows also encourage tree and shrub roots to the source of water, complicating and exacerbating the problem.
Poor roof plumbing can result in large volumes of rainwater being concentrated in a small area of soil:

- Incorrect falls in roof guttering may result in overflows, as may gutters blocked with leaves etc.
- Corroded guttering or downpipes can spill water to ground.
- Downpipes not positively connected to a proper stormwater collection system will direct a concentration of water to soil that is directly adjacent to footings, sometimes causing large-scale problems such as erosion, saturation and migration of water under the building.

Seriousness of Cracking

In general, most cracking found in masonry walls is a cosmetic nuisance only and can be kept in repair or even ignored. The table below is a reproduction of Table C1 of AS 2870.

AS 2870 also publishes figures relating to cracking in concrete floors, however because wall cracking will usually reach the critical point significantly earlier than cracking in slabs, this table is not reproduced here.

Prevention/Cure

Plumbing
Where building movement is caused by water service, roof plumbing, sewer or stormwater failure, the remedy is to repair the problem. It is prudent, however, to consider also rerouting pipes away from the building where possible, and relocating taps to positions where any leakage will not direct water to the building vicinity. Even where gully traps are present, there is sometimes sufficient spill to create erosion or saturation, particularly in modern installations using smaller diameter PVC fixtures. Indeed, some gully traps are not situated directly under the taps that are installed to charge them, with the result that water from the tap may enter the backfilled trench that houses the sewer piping. If the trench has been poorly backfilled, the water will either pond or flow along the bottom of the trench. As these trenches usually run alongside the footings and can be at a similar depth, it is not hard to see how any water that is thus directed into a trench can easily affect the foundation's ability to support footings or even gain entry to the subfloor area.

Ground drainage
In all soils there is the capacity for water to travel on the surface and below it. Surface water flows can be established by inspection during and after heavy or prolonged rain. If necessary, a grated drain system connected to the stormwater collection system is usually an easy solution.

It is, however, sometimes necessary when attempting to prevent water migration that testing be carried out to establish watertable height and subsoil water flows. This subject is referred to in BTF 19 and may properly be regarded as an area for an expert consultant.

Protection of the building perimeter
It is essential to remember that the soil that affects footings extends well beyond the actual building line. Watering of garden plants, shrubs and trees causes some of the most serious water problems.

For this reason, particularly where problems exist or are likely to occur, it is recommended that an apron of paving be installed around as much of the building perimeter as necessary. This paving

CLASSIFICATION OF DAMAGE WITH REFERENCE TO WALLS

Description of typical damage and required repair	Approximate crack width limit (see Note 3)	Damage category
Hairline cracks	<0.1 mm	0
Fine cracks which do not need repair	<1 mm	1
Cracks noticeable but easily filled. Doors and windows stick slightly	<5 mm	2
Cracks can be repaired and possibly a small amount of wall will need to be replaced. Doors and windows stick. Service pipes can fracture. Weathertightness often impaired	5–15 mm (or a number of cracks 3 mm or more in one group)	3
Extensive repair work involving breaking-out and replacing sections of walls, especially over doors and windows. Window and door frames distort. Walls lean or bulge noticeably, some loss of bearing in beams. Service pipes disrupted	15–25 mm but also depend on number of cracks	4

Gardens for a reactive site



should extend outwards a minimum of 900 mm (more in highly reactive soil) and should have a minimum fall away from the building of 1:60. The finished paving should be no less than 100 mm below brick vent bases.

It is prudent to relocate drainage pipes away from this paving, if possible, to avoid complications from future leakage. If this is not practical, earthenware pipes should be replaced by PVC and backfilling should be of the same soil type as the surrounding soil and compacted to the same density.

Except in areas where freezing of water is an issue, it is wise to remove taps in the building area and relocate them well away from the building – preferably not uphill from it (see BTF 19).

It may be desirable to install a grated drain at the outside edge of the paving on the uphill side of the building. If subsoil drainage is needed this can be installed under the surface drain.

Condensation

In buildings with a subfloor void such as where bearers and joists support flooring, insufficient ventilation creates ideal conditions for condensation, particularly where there is little clearance between the floor and the ground. Condensation adds to the moisture already present in the subfloor and significantly slows the process of drying out. Installation of an adequate subfloor ventilation system, either natural or mechanical, is desirable.

Warning: Although this Building Technology File deals with cracking in buildings, it should be said that subfloor moisture can result in the development of other problems, notably:

- Water that is transmitted into masonry, metal or timber building elements causes damage and/or decay to those elements.
- High subfloor humidity and moisture content create an ideal environment for various pests, including termites and spiders.
- Where high moisture levels are transmitted to the flooring and walls, an increase in the dust mite count can ensue within the living areas. Dust mites, as well as dampness in general, can be a health hazard to inhabitants, particularly those who are abnormally susceptible to respiratory ailments.

The garden

The ideal vegetation layout is to have lawn or plants that require only light watering immediately adjacent to the drainage or paving edge, then more demanding plants, shrubs and trees spread out in that order.

Overwatering due to misuse of automatic watering systems is a common cause of saturation and water migration under footings. If it is necessary to use these systems, it is important to remove garden beds to a completely safe distance from buildings.

Existing trees

Where a tree is causing a problem of soil drying or there is the existence or threat of upheaval of footings, if the offending roots are subsidiary and their removal will not significantly damage the tree, they should be severed and a concrete or metal barrier placed vertically in the soil to prevent future root growth in the direction of the building. If it is not possible to remove the relevant roots without damage to the tree, an application to remove the tree should be made to the local authority. A prudent plan is to transplant likely offenders before they become a problem.

Information on trees, plants and shrubs

State departments overseeing agriculture can give information regarding root patterns, volume of water needed and safe distance from buildings of most species. Botanic gardens are also sources of information. For information on plant roots and drains, see Building Technology File 17.

Excavation

Excavation around footings must be properly engineered. Soil supporting footings can only be safely excavated at an angle that allows the soil under the footing to remain stable. This angle is called the angle of repose (or friction) and varies significantly between soil types and conditions. Removal of soil within the angle of repose will cause subsidence.

Remediation

Where erosion has occurred that has washed away soil adjacent to footings, soil of the same classification should be introduced and compacted to the same density. Where footings have been undermined, augmentation or other specialist work may be required. Remediation of footings and foundations is generally the realm of a specialist consultant.

Where isolated footings rise and fall because of swell/shrink effect, the homeowner may be tempted to alleviate floor bounce by filling the gap that has appeared between the bearer and the pier with blocking. The danger here is that when the next swell segment of the cycle occurs, the extra blocking will push the floor up into an accentuated dome and may also cause local shear failure in the soil. If it is necessary to use blocking, it should be by a pair of fine wedges and monitoring should be carried out fortnightly.

This BTF was prepared by John Lewer FAIB, MIAMA, Partner, Construction Diagnosis.

The information in this and other issues in the series was derived from various sources and was believed to be correct when published.

The information is advisory. It is provided in good faith and not claimed to be an exhaustive treatment of the relevant subject.

Further professional advice needs to be obtained before taking any action based on the information provided.

Distributed by

CSIRO PUBLISHING PO Box 1139, Collingwood 3066, Australia

Freecall 1800 645 051 Tel (03) 9662 7666 Fax (03) 9662 7555 www.publish.csiro.au

Email: publishing.sales@csiro.au

© CSIRO 2003. Unauthorised copying of this Building Technology file is prohibited